

* Delta Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. S., R. 23 W.	* L-2
2. PROPERTY CONTROLLING IN SECTION	1, T. 41 N. S., R. 23 W.	* 5, 12
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DATE OF FIELD STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—overlaid, in a field survey on August 27 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the instructions of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in the field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a court of law:

A. Description of original monument and any deficiencies and subsequent restoration:

- L-2 Center $\frac{1}{4}$ corner - Section 1, B.H.R. monument previously set in wrong position.
- 5 N $\frac{1}{16}$ corner on the N-S $\frac{1}{4}$ line of Section 1.
- 12 S $\frac{1}{16}$ corner on N-S $\frac{1}{4}$ line - Section 1.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-2 Re-set at intersection of N-S and E-W $\frac{1}{4}$ lines. Previously set in wrong position because of an error in setting the east $\frac{1}{4}$ corner - Section 1.
- 5 Re-set at prop. measurement between the center of Section and the north $\frac{1}{4}$ corner of Section 1. Previously set in the wrong position because of an error in setting the East $\frac{1}{4}$ corner of Section 1.
- 12 Re-Set M.P.O.L. between the center of section and the S $\frac{1}{4}$ corner of Section 1. Previously set in the wrong position because of an error in setting the east $\frac{1}{4}$ corner of Section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL - 1" pipe, 4" aluminum cap
- L-2 6" W. Birch - N16° - 17.2'; 8" Cedar - N24°E - 37.8'; 5" W. Birch - N55° - 20.7'
 - 5 10" Cedar - S4°W - 24.5'; 4" Cedar - S55°W - 16.7'; 7" Cedar - N41°W - 11.3'
 - 12 4" B. Ash - N24°E - 11.1'; 7" B. Maple - S71°E - 22.4'; 9" Cedar - S27°W - 21.5'; 4" B. Ash - N58°W - 20.45'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 10-10-79
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558