

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. S., R. <u>23</u> E. W.	<u>L-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	T. <u>41</u> N. S., R. <u>23</u> E. W.	<u>5, 12</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA Co.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 29 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- L-2 - Ctr.  $\frac{1}{4}$  cor. Not previously established
  - 5 - N 1/16 cor. on N - S  $\frac{1}{4}$  line " " "
  - 12-S 1/16 of Section 1 " " "

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- L-2 - Set at intersection of the E-W and N-S  $\frac{1}{4}$  lines of Section 1.
  - 5 - set at the proportionate mea. between the ctr. of Sec. and the N $\frac{1}{4}$  cor. of Section 1.
  - 12- Set mid point and on line between the ctr. post and the south  $\frac{1}{4}$  cor. of Section 1.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- L-2 1" pipe, 4" aluminum cap; 7" cedar N21°E - 49.2'; 6" w. birch N7°W - 28.9'; falls 39' north of N-W by S.E. pipe line.
  - 5 - 1" pipe, 4" aluminum cap; 9" cedar S6°W - 18.65'; 4" cedar S73°W - 13.8"; 6" cedar N32°W - 15.6' Falls 4' east of N-S fence
  - 12 1" pipe, 4" aluminum cap; 4" b. ash N18°W 6.9'; ; 6" r. maple S87°E - 19.8' ; 8" cedar S36°W - 17.3';

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_