

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION	1, T. 41 N. _____ S., R. 23 E. _____ W. _____	4, 8, 11
3. MISCELLANEOUS PROPERTY IN SECTION	_____, T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA Co.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on April 29 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- 4 - NW 1/16 of Section 1
 - 8 - W 1/16 cor. on the E - W 1/4 line.
 - 11 - SW 1/16 of Section 1
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- 4 - Set at the intersection of N - S and E - W 1/16 lines in the NW 1/4 of Sec. 1
 - 8 - M.P.O.L. Between the W 1/4 post and the center of section 1.
 - 11 - Set at the intersection of the N-S and E - W 1/16 lines in the SW 1/4 of Sec. 1
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- 4 - 1 1/2" pipe, 4" aluminum cap; 8" cedar S38°E - 39.6'; 7" tamarack S18°W - 19.8'; 10" spruce S27°E - 7.2'
 - 8 - 1" pipe, 4" aluminum cap; 4" x 4" cedar post; 7" poplar N14°W - 13.1'; 6" balsam S10°W - 28.7'; W. birch N53°E - 27.65'
 - 11 - 1" pipe, 4" aluminum cap; 8" w. birch N66°E - 4.55'; 10" cedar N76°W - 23.6'; 6" cedar S13°W - 33.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____