

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. S., R. <u>23</u> E. W.	H-1, I-1, I-2
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 19 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-1 North $\frac{1}{4}$ corner - Sec. 3; I.D. by 4 stakes driven alongside set new cedar stake (McNabb). B.T. Stake - N45°E - 60.0'; B.T. Stake - S45°W - 35.0'; 61.5' north of center line of R.R.
- I-1 N.E. Section corner - Sec. 3; Cedar stake (McNabb); Cedar B.T. Stake - N45°E - 38.85'; Cedar B.T. Stake - S45°W - 35.7'; 76.5" north of centerline of R.R.
- I-2 East $\frac{1}{4}$ corner - Sec. 3; Set by Brotherton (1910); Corner material not stated; N.B.T.s; Cedar Stp. 14 - N 10 ft.; Cedar Stp. 14 - N50°W - 17.2'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-1 Corner is 19.25' South of centerline of County road. Set at McNabb's record mea. north of centerline of old R.R. grade and in line with old fence south, which fits McNabb's record of mea. east and west reasonably well.
- I-1 Corner is 6.75' south of county road centerline set at McNabb's record mea. north of centerline of old R.R. grade and in line with old fence south which fits reasonably well with McNabb's record of mea. E and W.
- I-2 Found old square scribed stake and both of Brotherton's old cedar stp. N.T.B.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-1 1" pipe, 4" aluminum cap (buried); 10" W. Birch - S59°W - 32.08'; 8" Fence Cor. Post - S74°E - 41.35'; Power pole - N62°E - 134.45'; Power pole - N31°W - 77.70'.
- I-1 $\frac{1}{2}$ " pipe & Pl. B.L.S. cap; 12" Tamarack - N53°W - 136.40'; 4" R. Maple - N1°E - 79.30'; 6" Cedar - S21°E - 32.69'; 4" Cedar - S4°W - 38.28'.
- I-2 1" pipe, 4" aluminum cap; 4" Spruce - N43°E - 5.55'; 6" Balsam Fir - N51°W - 21.20'; 8" Spruce - S73°W - 10.90'; 3" Balsam Fir - S2°W - 9.70'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-27-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558