

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. S., R. <u>23</u> E. W.	<u>F-1, G-1</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Rabbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram--over) were, in a field survey on July 19 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
F-1 North $\frac{1}{4}$ corner - Sec. 4; Cedar Stake (McNabb); B.T. Stake - N45°E - 63.0'; B.T. Stake - West - 63.0'; 61.5' North of centerline of R.R.

G-1 N.E. Section corner - Sec. 4; Cedar Stake (McNabb); B.T. Stake - N45°E - 38.0'; B.T. Stake - S45°W - 32.0'; 77.0' North of centerline of R.R.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
F-1 Corner is 18.55' South of centerline of County Rd. Set at McNabb's record mea. north of the centerline of old R.R. grade and in line with a fence north which fits McNabb's record of mea. east and west reasonably well.

G-1 Corner is 3.90' South of County rd. centerline - set at McNabb's record mea. north of centerline old R.R. grade and in line with old fences north and south which fit reasonably well with McNabb's record of mea. east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
F-1 3/4" Iron Bar - 24"; 8" Cedar - S32°W - 92.75'; Fence Cor. North - 54.20'; West end of Culvert - N56°E - 82.30'; Power pole - N58°W - 134.55'.

G-1 1/2" Pipe & Pl. R.L.S. Cap.; 6" Aspen - S12°W - 52.95'; 8" W. Birch - S10°E - 67.25'; Power Pole - N59°E - 92.20'; Fence corner North - 38.50'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Rabbitt CHIEF OF SURVEY PARTY DATE 12-27-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558