

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. S., R. <u>23</u> E. W.	<u>I-3, J-1, J-3</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on December 1 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- I-3 S.W. corner - Section 2; N.B.T.'s - D.A. Brotherton - 1910; Tam. 5 - N.- 13.2'; Tam. 5 - W. - 10.5'.
 - J-1 North $\frac{1}{4}$ corner - Section 2; Marked stake $\frac{1}{4}$ south (M. McNabb notes) 66.4' north of center of railroad; Cedar Stp. 14" - N49°30'E - 62.9'; Cedar Stk. marked "B.T." "5" - S49°30'W - 30.0'.
 - J-3 South $\frac{1}{4}$ corner - Section 2; Wood Post; Tam. 14 - N45°W - 8 lks.; Do. 8 - S70°E - 14 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- I-3 Set by retracing old survey by D.A. Brotherton for Gibbs & Sons in May of 1910. County records Pg. 47 extended line from the N.W. section corner across the West $\frac{1}{4}$ corner and prop. measurements to his record to match the prop. found in the north $\frac{1}{2}$ mile. No sign of Brotherton's N.B.T.'s or post.
 - J-1 Found nest of rocks in original soil beneath road shoulder 17' south of centerline of road old fence north - 66.4' north of centerline of old railroad grade as recorded in survey notes of M. McNabb also fits reasonably well with McNabb measurements east and west. Adjacent property owner states that C.C.C. men pulled McNabbs stake and threw it away in the 1930's.
 - J-3 See M.P.O.L. between the S.W. and S.E. section corners of Section 2.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- I-3 1" pipe, 4" aluminum cap; 5" Cedar - N40°W - 1.0'; 5" Cedar - N29°E - 21.8'; 5" Cedar - S87°E - 13.9'; 5" Cedar - S18°W - 5.4'.
 - J-1 1" pipe, 4" aluminum cap flush with road shoulder; 9" Tamarack - S36°W - 33.5'; 13" Tv. Top Tam. - South - 28.7'; 8" Cedar - S10°E - 23.8'; 10" Tam. - S42°E - 38.4'.
 - J-3 1" pipe, 4" aluminum cap; 10" Cedar - N27°W - 18.2'; 5" W. Birch - N29°E - 22.9'; 9" Cedar - S40°E - 39.7'; 8" Cedar - S13°E - 40.2'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR DATE 1-26-81 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558