

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA CO.

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 23 W.	H-7, G-7
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 22, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

North 1/4 corner of Sec. 22; wood post - burnt spruce 6" - S18°E - 25 lks.; burnt Tam. 6" - N35°W - 15 lks.

N.W. Sec. corner of Sec. 22; wood post - basswood - 20" - S55°E - 26 lks.; cedar - 16" - N40°W - 20 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Set M.P.O.L. between the N.E. and N.W. Sec. corners of Sec. 22. No sign of O.B.T.s.

Set by single prop. mea. N & S using the N.E. cor. of Sec. 33 and the N.E. cor. of Sec. 4 and at record G.L.O. Dist. (adjusted for average difference betw. mea. and G.L.O. record on 10 miles of line in this twp.) to the S. 1/4 cor. of Sec. 16 West. This method based on the 1947 Manual of Surveying Instructions, page 294, Sec. 371 and page 306, Sec. 383. It is true that there is a G.L.O. record dist. for 1 mile east of this corner but no sign of either the 1/4 corner or the Sec. Cor. could be found and the next mile was not run on the original survey; hence, nothing to proportion to going East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Mon. 7" Aspen - S47°W - 19.3'; 6" Balsam - S56°E - 6.45'; 8" Spruce - N40°E - 38.55'; 5" Spruce - N11°W - 40.04'.

D.N.R. Mon. 4" Maple - S77°E - 45.1'; 15" Y. Birch - N31°E - 61.8'; 4" Balsam - N30°W - 12.25'; 4" Maple - N76°W - 10.3'.

SIGNED BY

David B. Babbitt

DATE 12-22-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)