

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA CO.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY-----	T. 41 ^{N.} W. , R. 23 ^{W.}	E-3, G-3
2. PROPERTY CONTROLL- ING IN SECTION-----	, T. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION-----	, T. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO.-----, RECORDED PLAT-----		
5. PRIVATE CLAIMS-----		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 22, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 3 North 1/4 corner of Section 9; wood post - Tam. 9" - N25°W - 10 lks.; DO 8" - South - 17 lks.
- 3 N.E. corner of Section 9; wood post - Cedar - 9" - N30°E - 5 lks.; DO 8" - S45°W - 25 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 3 Set by prop. mea. between the N.E. and N.W. Sec. cors. of Sec. 9. But the N-S position controlled by a found line tree 10.00 chs. east. It is 29.6' south of a straight line from section corner to section corner.
- 3 Set by double prop. measurement using section corners, 1 mile East - 1 mile West - 1 mile North and 4 miles South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3 1" pipe, 4" aluminum cap; 6" Cedar - N37°E - 36.8'; 8" Cedar - S60°E - 20.7'; 10" Cedar - S63°W - 24.6'; 5" Cedar - N73°W - 14.5'.
- 3 1" pipe, 4" aluminum cap; 4" Cedar - N45°W - 9.0'; 8" Cedar - N35°E - 6.5'; 8" Cedar - S3°W - 5.8'; 5" Cedar - S68°E - 7.2'.

SIGNED BY

David B. Babbitt

DATE 12-22-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)