

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA CO.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>X</u> , R. <u>23</u> W. <u>X</u>	H-9, I-7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 22, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 9 South 1/4 of Section 22; not previously established.
- 7 N.E. Section Corner of Sec. 22; wood post - Burnt Tam. 8" - S43°W - 18 lks.; Burnt Tam. 11" - N30°E - 22 lks.; Swamp burnt over and trees killed.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 3 Set M.P.O.L. between the S.W. and S.E. Sec. corners of Sec. 22. This mile of line between Secs. 22 and 27 was not run and this corner was never established on the original Government survey.
- 7 Set by single prop. mea. N. & S. using the N.E. corner of Sec. 34 and the N.E. corner of Sec. 15 and at the record G.L.O. Dist. (adjusted for average difference between mea. and G.L.O. record on 10 miles of line in this township) to the S. 1/4 corner of Sec. 16 West. This method based on the 1947 Manual of Surveying Instructions, page 294, Sec. 371 and page 306, Sec. 383. The line East between Secs. 14 & 23 was not run on the original Govt. survey because of burnt swamp and windfall.

- 5 C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1" pipe, 4" aluminum cap. 6" Maple - S46°W - 3.5'; 6" Balsam - N65°E - 12.9'; 7" Balsam - S52°E - 14.6'; 10" Maple - S06°W - 29.5'.
- 7 D.N.R. Mon. 5" Balsam - S20°E - 7.1'; 13" Tam. - S43°E - 8.3'; 12" Balsam - S63°W - 66.8'; 10" Spruce - S60°W - 98.0'; 8" Balsam - N86°W - 77.75'.

SIGNED BY _____

David B. Babbitt

DATE 12-22-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)