

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*DELTA CO.*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ N. _____ E. _____ S., R. _____ W.	_____
2. PROPERTY CONTROLLING IN SECTION	9, T. 41, N. 23, R. 23, W. 7, 14, 16	7, 14, 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 22, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

North 1/16 East Boundary, Section 9; not previously established.

South 1/16 on East Boundary, Section 9; not previously established.

East 1/16 on South Boundary, Section 9; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Set M.P.O.L. between the N.E. Section corner and the E. 1/4 corner of Section 9.

Set M.P.O.L. between the E. 1/4 corner and the S.E. Section corner of Section 9.

Set M.P.O.L. between the S. 1/4 corner and the S.E. Section corner of Section 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe, 4" aluminum cap

5" R. Maple - S75°E - 24.3'; 6" Balsam - S8°E - 26.1'; 8" (Triple) R. Maple - S71°W - 47.3'; 6" Balsam - N5°W - 11.5'.

4" Balsam - N12°E - 123.50'; 2" W. Spruce - S74°E - 86.8'; 5" R. Maple - S58°W - 87.8'; 3" Aspen - N48°W - 5.7'.

7" Balsam - N14°W - 57.0'; 3" Balsam - N80°E - 33.6'; 5" B. Ash - S69°E - 55.8';

4" B. Ash - S39°W - 14.7'.

SIGNED BY

*David B. Babbitt*

DATE 12-22-81