

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. S., R. <u>23</u> E. W.	G-9 & G-10
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 27, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-9 - N.W. corner of Section 27; wood post - burnt Hemlock 9" - South - 20 lks;
burnt Balsam 5" - N15°W - 15 lks.

G-10 - West 1/4 corner of Section 27; wood post - burnt Cedar 6" - S45°E - 8 lks;
burnt Cedar 8" - N28°W - 25 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-9 - Found no sign of original survey evidence. Set by single prop. mea. N & S using the N.E. corner of Sec. 4 and at G.L.O. record dist. (adjusted for average difference between the mea. and G.L.O. record on 10 miles of line in this twp.) to the N.W. corner of Section 28. 1 mile west. This method based on the 1947 manual of surveying instructions, page 294, sec. 371 and page 306, sec. 383. The north line of Sec. 27 was not run on the original Gov't survey due to "burnt swamp". Hence nothing to proportion to going East.

G-10 - Set M.P.O.L. between the S.W. and N.W. Sec. corners of Section 27.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 - 1" pipe, 4" aluminum cap; 4" B. Spruce - S12°E - 13.1'; 4" Tamarack - S74°E - 12.8'
4" Tamarack - N20°E - 5.2'; 3" Tamarack - S70°W - 7.4'.

G-10 - 1" pipe, 4" aluminum cap; 4" Tamarack - N6°E - 19.1'; 10" Tamarack - S44°E - 29.7';
10" Tamarack - S5°E - 12.3'; 4" Cedar - S50°W - 22.8'.

SIGNED BY

David B. Babbitt

DATE

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: