

**LAND CORNER RECORDATION CERTIFICATE**

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

*DELTA*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>41</u> N. S., R. <u>23</u> E. W.		<u>F-9</u>
2. PROPERTY CONTROLL- <u>21</u> , T. <u>41</u> N. S., R. <u>23</u> E. W. ING IN SECTION _____		<u>15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 27, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-9 - South 1/4 corner of Section 21; wood post - burnt tam. 6" - North - 23 lks; burnt balsam 8" - S14°W - 28 lks.
- 15 - W 1/16 corner on the south section line of section 21; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-9 - Set M.P.O.L. between the S.E. and S.W. section corners of Section 21.
- 15 - Set M.P.O.L. between the S.W. section corner and the south 1/4 corner of Section 21.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-9 - 1" pipe, 4" aluminum cap; 12" B. spruce - N59°E - 40.0'; 8" cedar - S42°E - 20.3'; 10" cedar - S1°E - 44.6'; 7" tamarack - N71°W - 14.0'.
- 15 - 1" pipe, 4" aluminum cap; 14" B. spruce - N16°W - 21.1'; 11" cedar - S82°W - 26.8'; 5" B. spruce - S10°W - 24.6'; 4" B. spruce - S57°E - 13.4'.

SIGNED BY

*David B. Babbitt*

DATE

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: