

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. S., R. <u>23</u> E. W.	<u>I-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 27, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

-9 -N.E. Section corner of Section 27; wood post - w. pine 36" - N89°E - 7.20 chs.
cedar 16" - S86°E - 7.16 chs.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-9 - Set on line from the S.E. corner of Section 27 extended across a very old cedar stub with blazes and axe marks on the N & S sides. These marks were made while the tree was living and appear to be old enough to have been made at the time of the original gov't. survey. If not, they have to have been made while the original survey was still plain. This stub is 3225 ft. north of the S.E. sec. corner. There is also a squared up tree at the approx. N. 1/16 corner and very nearly on this same line. No other signs of occupation were found. N-S position was determined by single proportion using the S.E. corner of Section 27 and the S.E. corner of Section 10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 - 1" pipe, 4" aluminum cap; 4" balsam - N18°E - 28.0'; 3" black ash - S64°E - 22.6'; 6" balsam - S11°W - 38.9'; 4" w. spruce - N61°W - 25.0'.

SIGNED BY

David B. Babbitt

DATE

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: