

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>41</u> N. S., R. <u>24</u> E. W.		<u>I-3, I-5, K-5</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 24 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- I-3 N.W. section corner - Sec. 11; Wood post, Lynn 14 - S55°W - 31 lks.; Cedar 14 - N67°E - 16 lks.
- I-5 S.W. section corner - Sec. 11; Wood post, Cedar 10 - N50°W - 16 lks.; Cedar 10 - S35°E - 14 lks.
- K-5 S.E. section corner - Sec. 11; Wood post, Cedar 14 - S28°E - 11 lks.; Bl. Ash 10 - N42°W - 30 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- I-3 Found sq. cedar post reported by local property owners to be a perpetuation of the original corner post and it is comparable with other corners in the area.
- I-5 Set by double prop. measurements using section corners 1 mile east - 1 mile north - 1 mile south and 4 miles west.
- K-5 Found sq. cedar post with large cedar stp. in place for the southeast O.B.T. shows signs of lower face but too far gone for scribing - also cedar stp. N.E. - facing corner with plain scribing appears to be an unrecorded witness of the G.L.O. survey of 1854.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL - 1" pipe, 4" aluminum cap.
- I-3 10" Cedar - N24°W - 31.45'; 12" Cedar - N16°E - 32.00'; 10" Cedar - S54°E - 37.4'; 12" Cedar - S47°W - 18.6'.
- I-5 5" W. Birch - N79°W - 7.4'; 11" Cedar - S2°E - 58.7'; 6" Cedar - N81°E - 40.3'; 6" Cedar - S57°E - 18.8'.
- K-5 7" Cedar - S30°W - 26.75'; 10" W. Birch - S38°E - 18.20'; 10" Cedar - N51°E - 8.35'; 12" Cedar - N04°E - 37.85'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-13-78  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558