

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. S., R. <u>24</u> E. W.	<u>A-5, B-5, C-6, C-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 15 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-5 N.W. Section corner; Wood post, Hemlock 18" - S48°W - 9 lks; Cedar 15" - N27°W - 40 lks.
- B-5 N¼ corner of Sec. 18; Wood post, Spruce 8" - S56°W - 32 lks; Cedar 12" - N44°E - 12 lks.
- C-6 East ¼ corner - Sec. 18; Wood post, Maple 8" - S58°E - 14 lks; Cedar 18" - N50°W - 38 lks.
- C-7 S.E. Section corner - Sec. 18; Wood post, Cedar 16" - S44°W - 27 lks.; Tamerack 12" - N46°E - 26 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-5 Found old 4"x4" square, scribed post several old blazed trees near noted in Sawyer Stoll notes of 1958 as being a "Sq. post with N.B.T.S." not of record but accepted by local property owners as being the true corner for many years. Fits well with other corners in the area.
- B-5 Set by single prop. measurement and on line between the N.W. and N.E. Sec. corners of Sec. 18.
- C-6 Set M.P.O.L. between the N.E. and S.E. section corners of Sec. 18.
- C-7 Found sq. cedar stake - no sign of O.B.T.s - fits G.L.O. calls to swamp north and east and fits well with other corners in the area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL - 1" pipe, 4" aluminum cap
- A-5 8" Hard Maple - N63°W - 6.40'; 6" Hard Maple - N44°E - 11.35'; 14" Hard Maple - S85°E - 12.00'
- 10" Hard Maple - S37°W - 34.15'.
- B-5 5" Cedar - N50°W - 15.9'; 4" Cedar - N3°W - 15.8'; 7" Cedar - S25°E - 4.7'; 3" Cedar - S86°W - 12.0'.
- C-6 8" Cedar - N82°W - 10.65'; 6" Cedar - N24°W - 23.5'; Tw. 5" Cedars - S84°E - 10.0'; 4" Cedar - S16°E - 2.3'.
- C-7 Cedar Post beside monument; 9" Cedar - N37°W - 1.9'; 10" Cedar - S21°W - 14.1'; 3" Cedar S33°E - 7.1'; 9" Cedar - N75°E - 19.7'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-13-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558