

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. S., R. <u>24</u> E. W.	<u>F-7, G-6, G-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on May 16 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- F-7 South $\frac{1}{4}$ corner; Wood post, Cedar 18 - S45°E - 11 lks.; Maple 14 - N15°W - 31 lks.
 - G-6 East $\frac{1}{4}$ corner - Sec. 16; Wood post, Cedar 16 - N64°E - 6 lks.; Cedar 10 - S38°W - 24 lks.
 - G-7 S.E. Section corner - Sec. 16; Wood post, Hemlock 14 - N38°E - 30 lks.; Cedar 18 - S40°W - 12 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- F-7 Found 2" pipe and old squared stake in line with centerline of road east and south not of record but fits occupation lines and the location of other corners in the area well.
 - G-6 Set M.P.O.L. between the N.E. and S.E. section corners of Sec. 16.
 - G-7 Set in centerline of E-W road and in line with old fence south. No other evidence available.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ALL - 1" pipe, 4" aluminum cap.
 - F-7 Cedar post beside monument; "P.K." nail in side of P.P. - N45°E - 49.3'; 6" Cedar - N66°W - 37.6'; 8" W. Birch - S46°W - 31.6'; 12" Spruce - S11°W - 38.35'.
 - G-6 13" Spruce - S30°W - 10.05'; 4" Cedar - S29°E - 8.5'; 4" Cedar - N25°W - 7.0'; 7" Cedar - N11 E - 20.8'.
 - G-7 D.N.R. Monument buried in road; 5" Balsam - S29°E - 54.05'; 6" Cedar - S1°W - 86.5'; 10" Cedar - S40°W - 55.8'; 6" Balsam - S18°W - 40.6'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt DATE 12-13-78
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558