

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. S., R. <u>24</u> E. W.	<u>G-5, H-3, H-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on November 1 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- G-5 S.W. section corner of Sec. 10; Wood post, Sugar 10 - S20°E - 40 lks.; Cedar 12 - N38°W - 27 lks.
 - H-3 North ¼ corner; Wood post, Cedar 10 - S65°E - 4 lks.; Cedar 8 - N68°W - 14 lks.
 - H-5 South ¼ corner - Sec. 10; Wood post, Tamerack 14 - S37°E - 24 lks.; Spruce 8 - N24°W - 13 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-5 Set by double prop. measurement using section corners 2 miles east - 2 miles north - 2 miles west and 1 mile south.
 - H-3 Found 3" x 3" cedar stake - both cedar O.B.T.s in place. Still living but with considerable dead wood in each tree.
 - H-5 Set M.P.O.L. between the S.E. & S.W. section corners of Sec. 10.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ALL - 1" pipe, 4" aluminum cap
- G-5 8" Cedar - N4°E - 8.15'; 8" Cedar - S63°E - 19.1'; 5" Cedar - N60°W - 30.3'; 11" Cedar - S74°W - 34.4'.
 - H-3 Cedar 6" - N64°W - 16.6'; Cedar 9" - N54°E - 22.1'; Cedar 16" - S18°W - 30.3'.
 - H-5 5" Tam. - S57°W - 19.7'; 4" Tam - S54°E - 9.15'; 4" Tam. - N49°W - 4.1'; 5" Tam. - N16°E - 26.5'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-13-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558