

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. S., R. <u>24</u> E. W.	<u>C-2, D-1, E-1</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 9 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-2** West 1/4 Corner; Wood post (Brotherton 1911); Cedar Stake - N45°E - 33 ft.; Cedar Stake - S45°W - 33 ft.
- D-1** N1/4 - Sec. 5; Wood post, Cedar 16 - N55°E - 14 lks.; Do. 12 - N16°W - 19 lks.
- E-1** N.E. Section corner - Sec. 5; Wood post, Cedar 8 - N27°E - 38 lks.; Do. 7 - N24°W - 54 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-2** Found old 3"x3" sq. cedar post (in junk pile) as described in old Sawyer Stoll records and set by D.A. Brotherton around 1911 - no sign of witness stakes.
- D-1** Found 2 old sq. cedar stakes, one scribed "1/4". Cedar stump with lower blaze plain but no legible scribe marks in place for N.E. O.B.T. replaced with D.N.R. monument.
- E-1** Found sq. scribed cedar post from which Cedar stump (axe marks) N61°E - 4.5'; Cedar stump (scribed B.T.) - S41°E - 6.9'; not of record but fits other corners in the area well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL** 1" pipe, 4" aluminum cap.
- C-2** Cedar Post beside monument; Twin 2" W. Pines - N80°W - 28.8'; 27" H. Maple - S78°W - 49.2'; 6" Poplar - North - 22.5'; 16" Balsam - N68°E - 24.3'.
- D-1** 10" Cedar - N66°W - 39.0'; 8" Cedar - N14°E - 56.1'; 4" R. Maple - S75°E - 24.2'; 5" W. Birch - S17°W - 19.3'.
- E-1** 6" Cedar - N48°E - 18.69'; 4" Cedar - S64°E - 13.21'; 10" Cedar - S83°W - 20.80'; 4" Cedar - N13°W - 18.85'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt DATE 12-13-78
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558