

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. S., R. <u>24</u> E. W.	<u>C-8, E-7, E-8</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 9 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-8** West $\frac{1}{4}$ corner - Sec. 20; Wood post, Hemlock 24 - N43°W - 28 lks; Cedar 12 - S45°E - 8 lks.
- E-7** N.E. Section corner - Sec. 20; Wood post, Cedar 14 - S70°E - 31 lks.; Hemlock 16 - N12°W - 16 lks.
- E-8** E. $\frac{1}{4}$ corner - Sec. 20; Wood post (original); Hemlock 24 - S12°E - 29 lks.; Hemlock 18 - N45°W - 38 lks. Wood post (Brotherton 1905); Hemlock 20 - S46°-30'E - 105 $\frac{1}{2}$ lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-8** Round old sq. cedar stake reported by the adjacent property owners to have been set from an original bearing tree - Sawyer Stoll notes from 1958 refer to a "Stake and possible original B.T." - mea. south to the Ford River fits G.L.O. call also. It fits well with other corners in the area.
- E-7** Set by double prop. mea. using $\frac{1}{4}$ corners $\frac{1}{2}$ mile east and $\frac{1}{2}$ mile south and sec. corners 1 mile west and 3 miles north
- E-8** Set in line with old fence west and in line with centerline of road north and east. This fits the record of a survey by Brotherton, dated 1907, in which he states that he had the original $\frac{1}{4}$ corner. His survey was for the road north from the $\frac{1}{4}$ corner. This position also fits well with other corners in the area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL** - 1" pipe, 4" aluminum cap.
- C-8** 10" Maple - N45°W - 58.9'; 11" W. Birch - N18°E - 36.3'; 5" Maple - S30°E - 40.8'; Maple - N02°W - 15.0'.
- E-7** 4" Balsam - N17°W - 16.7'; 16" W. Birch - S28°W - 10.2'; 8" Balsam - S11°W - 5.7'; 10" Balsam - N60°E - 1.15'.
- E-8** 7" W. Birch - N57°W - 123.4'; Ref. tag in power pole - N36°W - 45.1'; 6" Cedar - N65°E - 126.4'; 4" Cedar - S46°E - 83.8'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-13-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558