

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>41</u> N. S., R. <u>24</u> E. W.		<u>H-7, I-7</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 9 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-7 South $\frac{1}{4}$ corner; Wood post, Cedar 10" - S40°E - 10 lks.; Hemlock 10" - N70°W - 11 lks.
 I-7 S.E. Section corner; Wood post, Cedar 20" - N45°W - 22 lks.; Cedar 16" - S52°E - 42 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-7 Found 2"x2" cedar stake at old fence corner location is compatible with other corners in the area.
 I-7 Found 3"x3" square cedar stake and another old square stake, stumps in place for both O.B.T.s but too far gone to read. (Noted in old Sawyer-Stoll records).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL 1" pipe, 4" aluminum cap
 H-7 6" W. Birch - S42°W - 24.8'; 8" Cedar - N40°W - 29.0'; 4" Cedar (in clump) - N27°E - 23.1'; 7" Cedar - S86°E - 65.7'.
 I-7 8" Tam. - N16°E - 34.3'; 6" Spruce - S32°E - 13.9'; 6" Spruce - S23°W - 7.4'; 7" Tam. - N87°W - 66.4'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-13-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558