

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. S., R. <u>24</u> E. W.	<u>C-3, C-4, E-4</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 3 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- C-3** N.W. Section Corner; Wood post, Hemlock 10" - N40°E - 13 lks.; Spruce 12" - S55°W - 15 lks.
  - C-4** West ¼ corner; Wood post, Y. Birch 12 - S38°E - 37 lks.; Cedar 12 - N44°W - 11 lks. Wood post, noted by Ken Buckland P.E. on a drawing dated 1963, no N.B.T.s noted.
  - E-4** East ¼ corner - Sec. 8; Wood post, Cedar 18 - S40°E - 22 lks.; Cedar 8 - N58°W - 8 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- C-3** Set by projecting a line from the west ¼ corner across a pipe found for the N. 1/16 corner on the west sec. line and double the distance. Both the ¼ cor. & 1/16 cor. were noted in Sawyer Stoll records and in a 1963 survey drawing by Ken Buckland - but not recorded at the Register of Deeds.
  - C-4** Found old post point in the position indicated for a sq. post in a survey drawing by Ken Buckland - dated 1963 this falls in line with an old fence east and south.
  - E-4** Set M.P.O.L. between the NE & SE section corners of Sec. 8

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ALL** - 1" pipe, 4" aluminum cap
  - C-3** 12" Maple - N16°E - 63.6'; 7" Cedar - N53°E - 97.1'; 11" W. Birch - S48°W - 54.0'; 7" Balsam - N88°E - 18.7'.
  - C-4** Cedar post beside monument; 7" Maple - S73°E - 71.1'; 7" Maple - S07°E - 60.0'; 8" W. Birch - N63°W - 48.6'; 5" Bl. Ash - S34°W - 31.1'.
  - E-4** 5" Tamarack - N78°E - 31.9'; 13" Tamarack - N35°E - 25.4'; 4" B. Spruce - S21°E - 24.3'; 6" B. Spruce - N80°W - 18.4'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 12-13-78  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558