

SURVEY & REMONUMENTATION

OCT 26 1995

COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Sept 27, 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Walter C. Thomas
Chairman

For corners in
DELTA
(County)

Located In: Corner Code ##

- 1. Public Land Survey T 41 N R 19 W K-9 & K-10
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Recorded OCT - 5 1995
at 9:00 o'clock AM in Liber 8 Page 96

Walter C. Thomas Reg. of Deeds.
Delta County, Michigan

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims K-9 [NW COR SEC 25] K-10 [W1/4 COR SEC 25]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, H.P. DAVIS, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9 [NW COR SEC. 25] A. MERRYWEATHER, D.S. - 1849 - WOOD POST (CEDAR 08"-S60°W-06 LINKS) (CEDAR 14"-N10°E-21 LINKS) JOSEPH E. GINGRASS - 1906 - 1D CORNER POSITION FROM ORIGINAL BT'S - NO NEW WIT'S NOTED

K-10 [W1/4 COR SEC. 25] A. MERRYWEATHER, D.S. - 1849 - WOOD POST (BIRCH 14"-S20°W-14 LINKS) (BIRCH 10"-NORTH-10 LINKS) JOSEPH E. GINGRASS - 1906 - "RESET FROM ORIGINALS" NO NEW WIT'S NOTED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 [NW COR SEC. 25] FOUND IN PLACE THE REMAINS OF A SQUARED WOOD POST & BOTH "GLO" BT'S DOWN & IN POOR CONDITION, UPPER & LOWER FACE BLAZES EVIDENT, INTERIOR WOOD DECAYED TO THE POINT WHERE THE SCRIBING HAS DISAPPEARED. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

K-10 [W1/4 COR SEC. 25] FOUND IN PLACE AT THE JCT OF ANCIENT FARM FENCE LINES EAST & SOUTH THE REMAINS OF A SQUARED WOOD POST SCRIBED "1/4", NO EVIDENCE OF "GLO" OR SUBSEQUENT BT'S FOUND. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 REPLACED EXISTING MONUMENT WITH A BERNTSEN A1NB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO 1D THE CORNER POSITION.
 CEDAR 14" CEDAR 9" SPRUCE 7" CEDAR 12" SURVEY MONUMENT SIGN POST
 N85°E S16°E S68°W N47°W NORTH
 28.83' 42.46' 13.39' 20.50' 2.16' (TO FACE)

K-10 REPLACED EXISTING MONUMENT WITH A BERNTSEN A1NB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO 1D THE CORNER POSITION.
 W. BIRCH 13" CEDAR 12" CEDAR 10" SURVEY MONUMENT SIGN POST NOTE: CORNER IS IN OPEN PASTURE
 N62°W N10°E N60°E SOUTH
 37.48' 32.40' 27.61' 2.89' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 9/27/95
 Surveyor's Michigan License No. 16926