

OCT 26 1995
COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Sept 27, 1995
Robert Schmelzer
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
DELTA
(County)

Located In: Corner Code ##

- 1. Public Land Survey T 41 N R 19 W K-11 & K-12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Recorded OCT - 5 1995
at 9:00 o'clock AM in Liber 8 Page 97
Walter C. Thuman Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

K-11 [NW COR SEC 36] K-12 [W1/4 COR SEC 36]

I, M.P. DAVIS, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- K-11 [NW COR SEC. 36] A. MERRYWEATHER, D.S. - 1849 - WOOD POST (BEECH 07°-N41°W-13 LINKS) (SUGAR 06°-S50°W-11 LINKS)
JOSEPH E. GINGRASS - 1906 - ID CORNER POSITION FROM-NBT'S (MAPLE STUMP 12°-N52°E-14.5 LINKS) (MAPLE 14°-S30°?-39.3 LINKS)
 - K-12 [W1/4 COR SEC. 36] A.MERRYWEATHER, D.S. - 1849 - WOOD POST (BEECH 14°-N55°E-24 LINKS) (SUGAR 03°-S63°W-11 LINKS)
JOSEPH E. GINGRASS-1906-EST "1/2 DISTANCE BETWEEN CORNERS" NBT'S (?? N47°W-27 LINKS) (?? S2°E-16 LINKS)



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- K-11 [NW COR SEC. 36] NO EVIDENCE OF GLO'S OR GINGRASS'S 1906 BT'S FOUND, SURROUNDING AREA IS NOW OCCUPIED BY FARM FIELDS, CORNER POSITION ID BY LARGE CORNER FENCE POST (FENCE LINES N-S & E). DISTANCES TO ADJOINING CORNERS FIT WELL WITH THE RECORDS OF GINGRASS. ACCEPTED FENCE CORNER AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 - K-12 [W1/4 COR SEC. 36] NO EVIDENCE OF GLO'S OR GINGRASS'S 1906 BT'S FOUND, SURROUNDING AREA IS NOW OCCUPIED BY FARM FIELDS, CORNER POSITION ID BY LARGE CORNER FENCE POST (FENCE LINES E-W & S). DISTANCES TO ADJOINING CORNERS FIT WELL WITH THE RECORDS OF GINGRASS. ACCEPTED FENCE CORNER AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-11 SET, AT EXISTING FENCE CORNER, A BERNTSEN AINB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION.
BEECH 7" MAPLE 19" SURVEY MONUMENT SIGN POST NOTE: FARM FIELDS IN THE NE & SE QUADRANTS.
S60°W N07°W NORTH
18.89' 10.23' 2.19' (TO FACE)
 - K-12 SET, AT EXISTING FENCE CORNER, A BERNTSEN AINB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION.
IRONWOOD 13" BEECH 07" SURVEY MONUMENT SIGN POST NOTE: FARM FIELDS IN NE, SE & SW QUADRANTS
S55°E N83°E SOUTH
2.50' 15.76" 2.50' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 10/27/95
Surveyor's Michigan License No. 16926