

OCT 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Sept 27, 1995
Robert Schmalzer Acting Chairman

For corners in DELTA (County)

Located In: Corner Code #

- 1. Public Land Survey T 41 N R 19 W K-11 & K-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Recorded OCT - 5 1995 at 9:00 o'clock AM in Liber 8 Page 97
Walter C. Thuman Reg. of Deeds. Delta County, Michigan

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

K-11 [NW COR SEC 36] K-12 [W1/4 COR SEC 36]

I, M.P. DAVIS, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and two dots in row 12.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
K-11 [NW COR SEC. 36] A. MERRYWEATHER, D.S. - 1849 - WOOD POST (BEECH 07"-N41°W-13 LINKS) (SUGAR 06"-S50°W-11 LINKS) JOSEPH E. GINGRASS - 1906 - ID CORNER POSITION FROM-NBT'S (MAPLE STUMP 12"-N52°E-14.5 LINKS) (MAPLE 14"-S30°?-39.3 LINKS)
K-12 [W1/4 COR SEC. 36] A.MERRYWEATHER, D.S. - 1849 - WOOD POST (BEECH 14"-N55°E-24 LINKS) (SUGAR 03"-S63°W-11 LINKS) JOSEPH E. GINGRASS-1906-EST "1/2 DISTANCE BETWEEN CORNERS" NBT'S (?? N47°W-27 LINKS) (?? S2°E-16 LINKS)



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-11 [NW COR SEC. 36] NO EVIDENCE OF GLO'S OR GINGRASS'S 1906 BT'S FOUND, SURROUNDING AREA IS NOW OCCUPIED BY FARM FIELDS, CORNER POSITION ID BY LARGE CORNER FENCE POST (FENCE LINES N-S & E). DISTANCES TO ADJOINING CORNERS FIT WELL WITH THE RECORDS OF GINGRASS. ACCEPTED FENCE CORNER AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
K-12 [W1/4 COR SEC. 36] NO EVIDENCE OF GLO'S OR GINGRASS'S 1906 BT'S FOUND, SURROUNDING AREA IS NOW OCCUPIED BY FARM FIELDS, CORNER POSITION ID BY LARGE CORNER FENCE POST (FENCE LINES E-W & S). DISTANCES TO ADJOINING CORNERS FIT WELL WITH THE RECORDS OF GINGRASS. ACCEPTED FENCE CORNER AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-11 SET, AT EXISTING FENCE CORNER, A BERNTSEN AINB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION. BEECH 7" MAPLE 19" SURVEY MONUMENT SIGN POST NOTE: FARM FIELDS IN THE NE & SE QUADRANTS. S60°W N07°W NORTH 18.89' 10.23' 2.19' (TO FACE)
K-12 SET, AT EXISTING FENCE CORNER, A BERNTSEN AINB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION. IRONWOOD 13" BEECH 07" SURVEY MONUMENT SIGN POST NOTE: FARM FIELDS IN NE, SE & SW QUADRANTS S55°E N83°E SOUTH 2.50' 15.76" 2.50' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 10/27/95
Surveyor's Michigan License No. 16926