

OCT 26 1995

COMMISSION


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Sept 27, 1995
Chairman

For corners in DELTA (County)

Located In: Corner Code ##

- 1. Public Land Survey T 41 N R 19 W
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R



Recorded OCT - 5 1995 at 9:00 o'clock AM in Liber 8 Page 98

Reg. of Deeds. Delta County, Michigan

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

K-13 [SW COR SEC 36] L-9 [N1/4 COR SEC 25]

I, M.P. DAVIS, in a field survey on SEPTEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. Contains numbers 1-36 and some dots.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 [SW COR SEC. 36] JOHN BURT, D.S. - 1845 - WOOD POST (SUGAR 30°-N11°E-38 LINKS) (SUGAR 07°-N63°W-37 LINKS) JOSEPH E. GINGRASS - 1906 - CORNER IN PLACE-NBT'S (??-N65°E-29.0 LINKS) (??-S02°E-16.0 LINKS) M.S. McNABB-1920-STAKE & Y.BIRCH 12" BT (N70°W-18.5') IN PLACE-NBT BEECH N87°W-44.0'

L-9 [N1/4 COR SEC. 25] A.MERRYWEATHER, D.S. - 1849 - WOOD POST (BIRCH 28°-S70°W-10 LINKS) (CEDAR 08°-N47°E-19 LINKS) JOSEPH E. GINGRASS-1906-ID "FROM ORIGINALS" - NO NEW WIT'S NOTED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 [SW COR SEC. 36] NO EVIDENCE OF CORNER MONUMENT FOUND AS ALL HAS BEEN APPARENTLY DESTROYED BY COUNTY ROAD CONSTRUCTION. EXTENDED LINE WEST FROM SE COR S36 T41N R19W THRU THE N1/4 COR S3 T40N R19W AND ESTABLISHED CORNER POSITION ON THIS LINE AND 331.0' WEST OF SAID N1/4 COR. AS PER McNABB'S 1920 RECORDS OF HIS SUBDIVISION OF SAID SEC 3. ACCEPTED THIS POSITION AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

L-9 [N1/4 COR SEC. 25] NO EVIDENCE OF GLO'S BT'S OR GINGRASS'S 1906 CORNER FOUND. ID CN1/16 CORNER OF SECTION 25, BY GINGRASS'S 1906 IRON STAKE, EXTENDED LINE NORTH FROM S1/4 COR SEC 25 THRU THE CN1/16 AND ESTABLISHED THE 1/4 CORNER ON THIS LINE & AT A PROPORTIONATE DISTANCE NORTH OF THE CN1/16 CORNER. ACCEPTED THIS AS A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 SET, 6" BELOW ROAD SURFACE, A 5/8" X 18" REBAR W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION. IRONWOOD 05" RED PINE 10" HEMLOCK 18" SURVEY MONUMENT SIGN POST S37°W N57°W S37°E NORTH 43.86' 58.92" 48.75' 15.50' (TO FACE)

L-9 SET, 6" BELOW ROAD SURFACE, A 5/8" X 18" REBAR W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION. COR FENCE POST POWER POLE SURVEY MONUMENT SIGN POST NOTE: AREA SURROUNDED BY FARM S75°W S39°E NORTH FIELDS. NO OTHER WIT'S 32.90' (TO FACE) 58.23' (TO FACE) 19.17' (TO FACE) AVAILABLE.

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 9/27/95

Surveyor's Michigan License No. 16926