

SURVEY & REMONUMENTATION

JAN 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/18, 1997
M. P. Davis
Chairman

For corners in
DELTA
(County)

Located In: Corner Code #/

- | | | | | | | | |
|------------------------------------|---|----|---|---|----|---|------------------------|
| 1. Public Land Survey | T | 42 | N | R | 22 | W | <u>E-09 & E-10</u> |
| | T | | | R | | | |
| | T | | | R | | | |
| | T | | | R | | | |
| 2. Property Controlling in Section | S | | | T | | R | |
| | S | | | T | | R | |
| 3. Miscellaneous Property in Sec. | S | | | T | | R | |
| | S | | | T | | R | |

Dec 19 1997
9:00 AM
9 267

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims E-09 [NW SEC 28] E-10 [W1/4 SEC 28]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS in a field survey on DECEMBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
E-09 [NW COR SEC 28] E.C.MARTIN, DS - 1852 - WOOD POST - (Y.BIRCH 18°-S61°E-21 LINKS)(HEMLOCK 18°-N48°W 33 LINKS)
D.A.BROTHERTON-1910-FOR TWP. ROAD-SURVEY NOTES SHOW COR IN PLACE, NO DESCRIPTION OF EXISTING MONUMENT GIVEN OR BT'S NOTED
- E-10 [W1/4 COR SEC 28] E.C.MARTIN DS - 1852 - (CEDAR 12°-S80°W-16 LINKS)(SUGAR 06°-N62°E-12 LINKS)
D.A.BROTHERTON-1919-FOR TWP. ROAD-SURVEY NOTES SHOW CORNER IN PLACE, NO DESCRIPTION OF EXISTING MONUMENT GIVEN OR BT'S NOTED
M.S.McNABB-1939-IRON IN HWY. 1.5' NORTH OF FENCE EAST-FENCE POST EAST 24.5'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-09 [NW COR SEC 28] FOUND IN PLACE & 12" M/L BELOW ROAD SURFACE A 5/8" IRON PIPE AT APPROX. C/L INTERSECTION OF COUNTY ROAD N-S & E. NO ACCESSORIES FOUND. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.
- E-10 [W1/4 COR SEC 28] FOUND IN PLACE & 10" M/L BELOW ROAD SURFACE A 1/2" IRON BAR IN LINE WITH APPARENT OCCUPATION LINE TO THE EAST. FENCE LINE IS DOWN & IN POOR REPAIR. UNABLE TO IDENTIFY McNABB'S FENCE POST BT. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-09 SET, OVER EXISTING MON, A 5/8 X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION & RAISED TO GRADE W/A MON BOX
SPRUCE 12" TAMARACK 11" SPRUCE 06" ANCHOR POLE SURVEY MONUMENT SIGN POST
N35°W S26°E S32°W N41°E EAST
53.12' 76.34' 64.20' 35.59 19.88' (TO FACE)
- E-10 SET, OVER EXISTING MON, A 5/8 X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION & RAISED TO GRADE W/A MON BOX
SPRUCE 06" SPRUCE 08" RED PINE 11" SURVEY MONUMENT SIGN POST
N58°W S48°W S46°E EAST
38.72' 43.59' 52.61' 24.85' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/9/97
Surveyor's Michigan License No. 16926