

1. Public Land Survey T 42N R 22W B-7 ✓
 T 42N R 22W C-7 ✓
 T 42N R 22W C-6 ✓
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**DELTA
Co.**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 12/30/85 & 1/21-23, 19 86
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-7 South 1/4 corner of Section 18. Wood post. Maple 12" - S50W 14 lks.
 Cedar 12" - N30E 5 lks.

C-7 Southeast sec. corner of Section 18. Wood post. Lynn 16 - S58°E - 25 lks.
 W.Pine 10 - N54°W - 29 lks.

C-6 East 1/4 corner of Section 18. Wood post. W. Birch 10 - S40W - 22 lks.
 W. Birch 10 - N45E - 19 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 Set from stump remains of the northeast O.B.T. (12" cedar-N30°E-5 lks.) Callous
 around bottom blaze plain but face badly burned, no scribe marks visible. Mea. to
 stream 396 ft. west fits G.L.O. record very well.

C-7 Set by double proportion to the G.L.O. record using sec. cors. 1 mile north and 1 mile
 east and 1/4 cors. 1/2 mile south and 1/2 mile west.

C-6 Set M.P.O.L. between the NE and the SE section cors. of Section 18.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 D.N.R. Monument 4" Twin R. Maple S67°W 16.7' 9" Balsam Fir S64°E 2.55'
 7" Balsam Fir N34°W 1.25' 12" Spruce N39°E 14.45'

C-7 D.N.R. Monument 8" Sugar Maple S81°W 1.6' 10" R. Maple N67°E 25.0'
 8" Balsam Fir N23°W 17.9' 5" R. Maple S34°E 52.1'

C-6 D.N.R. Monument 13" Cedar S53°W 27.6' 7" Balsam Fir N19°E 21.7'
 12" Cedar N70°W 26.8' 5" R. Maple S37°E 21.9'

Signed by

David B. Babbitt

Date

2-11-86

Surveyor's Michigan License No. RLS 21558