

1. Public Land Survey T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S 17 T 42N R 22W 15. 16. 3.
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**DELTA
Co.**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 1/22&23, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

15. W 1/16 cor. on the south sec. line of Section 17. Not prev. est.

10. South 1/16 cor. on the W section line of Section 17. Not prev. est.

3. North 1/16 on West section line of Section 17. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

15. Set M.P.O.L. between the S 1/4 cor. and the SW sec. cor. of Section 17.

10. Set M.P.O.L. between the W 1/4 cor. and the SW sec. cor. of Section 17.

3. Set M.P.O.L. between the NW sec. cor. and the W 1/4 cor. of Section 17.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

15. D.N.R. Monument Cedar 6" N70°E 15.7 Cedar 8" S150°W 10.7
 Cedar 12" N16°W 24.0 Cedar 7" S55°E 13.0

10. D.N.R. Monument Cedar 9" S18°E 19.9' Cedar 10" N39°E 29.7'
 Cedar 7" S82°E 19.3' Cedar 8" N19°E 62.5'

3. D.N.R. Monument R. Maple 5" S57°W 2.6' Sugar Maple 4" N25°E 1.7'
 R. Maple 5" N79°W 10.4' Red Maple 10" East 6.4'

Signed by

David B. Babbitt

Date

2-11-86

Surveyor's Michigan License No.

RLS 21558