

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u> T. <u>42N</u> N. S., R. <u>22W</u> E. W.		<u>F-7, G-7</u>
2. PROPERTY CONTROLL- ING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**DELTA
CO.**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9/26/85, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

F-7. South 1/4 cor. of Section 16.

Wood post.

Spruce 14 - S58W - 7 Lks.

Spruce 8 - N22E - 21 Lks.

G-7. SE sec. cor. of Section 16.

G.L.O. Record

Wood post.

Cedar 12" - S50°E - 25 Lks.

Cedar 8" - N60°W - 28 Lks.

USFS Record.

A stake. Metal location poster is on a cedar tree 4" in dia. on the W side of tree from which this cor. bears East 7 lks or re-establishing corner: 2 B.T. trees

B. Description of corner evidence found and/or method applied in restoring

F-7. Set M.P.O.L. between the SE and SW section cors. of Section 16. Old streambed is 1.40 chs. east which is the exact distance recorded in the notes of the original Gov't. survey.

G-7. Found sq. post and 3 older post bottoms with cedar stumps in place for both O.B.T.'s. Forest Service tag on cedar 7 lks. west of post. Forest Service record noted "2 B.T. trees" in 1937.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7. D.N.R. Monument

10" cedar N30°E - 58.7'

8" H. maple N27°W - 44.65'

10" H. maple S32°E - 4.0'

9" H. maple N70°W - 56.4'

G-7. D.N.R. Monument

8" cedar S8°E - 21.9'

9" cedar S63°W - 3.2'

4" cedar N26°W - 21.0'

4" cedar N83°E - 23.2'

3"x3" sq. post (Champion into tag on tree nearby) N42°W - 40.6'

SIGNED BY

David B. Babbitt

DATE

2-11-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)