

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>42</u> N. _____ S. _____ R. <u>22</u> E. _____ W. _____	<u>5, 9, 12</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**DELTA
Co.**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on July 14 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
5 - N 1/16 corner on N-S 1/4 line; not previously established.

9 - E 1/16 corner on E-W 1/4 line; not previously established.

12 - S. 1/16 corner on N-S 1/4 line; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

5 - Set at computed position by closed traverse. M.P.O.L. between center and N 1/4 corner.

9 - Set at computed position by closed traverse. M.P.O.L. between center and E 1/4 corner.

12 - Set at computed position by closed traverse. M.P.O.L. between center and S 1/4 corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
ALL - 1" pipe, 4" aluminum pipe and cedar post.

5 - 6" w. birch - N43°W - 4.5'; 3" cedar - N85°E - 27.5'; 8" cedar - S51°E - 33.2';
3" cedar - S21°E - 27.35'

9 - 6" balsam - S58°W - 23.05'; 6" maple - S10°W - 112.8'; 6" w. pine - N31°W - 81.3';
13" spruce - S29°W - 52.5'

12 - 9" spruce - S8°E - 35.35'; 5" balsam - S62°W - 21.5'; 9" spruce - N34°W - 33.2';
9" spruce - N67°E - 7.3'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558