

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. S., R. <u>22</u> E. W.	K-6, L-7, <del>M-7</del> <sup>K-7</sup>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**DELTA Co.**

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 20 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

K-6 West  $\frac{1}{4}$  corner Wood post - Hem. 18 - S38°W - 24 lks.; Hem. 14 - N30°E - 4 lks.

L-7 South  $\frac{1}{4}$  corner Wood stake - M. McNabb (1916); B.T. Stake - NW 33'; B.T. Stake SW 33'

<sup>to W.T.</sup> ~~M-7~~ <sup>K-7</sup> S.W. section corner; 1" iron rod - R. Schmeling - 1967; 9" y. birch - S13°W - 43.3'; 16" W. cedar - south - 34.2'; 14" hemlock - N22°W - 67.7'; all mea. to centerline of tree. (our mea. to face of tree)

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

K-6 Nothing found - set mid point on line between the N.W. and S.W. section corners.

L-7 Nothing found - set mid point on line between the S.W. and S.E. section corners found in north track of E-W trail road & in line with old fence south. Fits reasonably well with old record by M. McNabb in Sec. 24 - dated 1916

M-7 Set mon. in centerline of E-W road from N.B.T.s by Robert Schmeling (1967) his iron rod was graded out.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-6 1" pipe, 4" aluminum cap; 10" maple - S22°W - 25.7'; 18" TW. Maple - N30°E - 12.2'; 12" W. birch - S64°E - 22.5'; S.E. corner of cabin - N43°W - 117.3'

L-7 6" Maple (in clump) - S72°E - 58.5'; 5" spruce - S14°W - 45.25'; 12" W. birch - N84°W - 114.7'; 5" balsam - N15°E - 62.1'

M-7 1" pipe, 4" aluminum cap (buried in road); Old N.B.T.s { 17" cedar - S2°W - 33.6'  
10" y. birch - S13°W - 41.9'  
15" hemlock - N22°W - 67.0'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558