

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. S., R. 22 E. W.	L-5, M-5, M-6
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA Co.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 23 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-5 N 1/4 corner; nothing found
- M-5 N.E. section corner; Cedar stake - M. McNabb - 1913; B.T. stake - NW - 33'; B.T. stake - SE - 33'
- M-6 E. 1/4 corner; wood stake - M. McNabb - 1913; no wits. recorded

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-5 Nothing found - set mid point on line between the N.E. and N.W. section corners - falls near south edge of graded portion on E-W road.
- M-5 Nothing found - set by proportion to record of survey by M. McNabb north & south - in centerline of road intersection and in line with old fence east.
- M-6 Nothing found - set by prop. to record of survey by M. McNabb dated 1913 - falls in approx. centerline of N-S road and in line with an old fence line west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL - 1" pipe; 4" aluminum cap
- L-5 4" h. maple - N4°E - 39.92'; 8" apple tree - S61°W - 48.60'; 12" h. maple - N61°E - 57.97'; power pole - S35°E - 33.35'
- M-5 8" tamarack - S84°W - 128.3'; 10" w. spruce - N49°E - 92.5'; 9" r. maple - S83°E - 84.2'; power pole S.35°E - 31.3'
- M-6 Power pole - S35°E - 53.45'; 9" h. maple - S36°W - 68.60'; telephone junction box - N60°E - 42.90'; 12" h. maple - N19°W - 59.80'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558