

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>4</u> T. <u>42</u> N. S., R. <u>22</u> E. W.		<u>G-3</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

*DELTA  
CO.*

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on September 8, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

G-3 S.E. Section Corner - *SEC. 4*  
 Wood post  
 Tam. 30-S80°E - 16 links  
 Do. 30-N30°W - 10 links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

G-3 Found 3"x3" square cedar stk. with smaller stake point beside it. Tam. stps. in place for both O.B.T.S trunks of both trees on ground N.W. one in fair condition but fallen on its face could not get under it to look for marks but I could feel the upper face with my fingers. This corner located and verified by U.S.F.S. in 1964.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-3 1" pipe, 4" aluminum cap  
 6" cedar - S31°E - 7.4'  
 6" cedar - N47°E - 4.9'  
 12" cedar - N30°W - 9.6'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)