

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>14</u> T. <u>42</u> N. S. R. <u>22</u> K. W.		K-5 J-5
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA
CO.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on _____ 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 21 1975, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<p>J-5 Original Monument & Access Wood Post Fir 10-S65°W - 26 lks. Cedar 10-N44°E - 17 lks.</p>	<p>K-5 Original Wood Post Tam. 12-s56°E - 22 lks. Cedar 14-N16°W - 24 lks.</p>
---	--

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>J-5 Found by Mike Zuidema. Post at corner has U.S.F.S. property boundary and attention sign warning of penalties for destruction or removal of corner on b.t.s. Corner set and witnessed by unknown party. Blown down cedar fits position and description of N.E.-O.B.T. blaze plain - over-</p>	<p>grown about 4" K-5 Set from 16" tam stump for S.E. O.B.T. - center rotted but hack mark and lower blaze plain on overgrowth.</p>
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>J-5 8" Cedar (BT) N83°W, 30.6' 8" Cedar (BT) S52°W, 8.6' 11" Cedar (BT) south, 34.0' 18" blown down cedar - N44°E, 11.2'</p>	<p>K-5 4" Cedar - S05°E, 19.0' 6" cedar - N13°E, 35.5' Falls in line with centerline road east about 5' west of fence north.</p>
---	--

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE October 22, 1975
MICHIGAN REGISTERED LAND SURVEYOR