

ok 2/8

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Delta</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T 42N R 22W	D-7	Register of Deeds Stamp & File Number
	T 42N R 22W	E-6	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 1/27, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| D-7. South 1/4 corner of Section 17.
Wood post.
Cedar 6" - S75W - 23 Lks.
Tamarack 12" - N15E - 16 Lks. | E-6. East 1/4 corner of Section 17.
Wood post.
Hemlock 12" - S77E - 14 Lks.
Cedar 10" - N52W - 22 Lks. |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-7. Set M.P.O.L. between the SE and SW section corners of Section 17.
- E-6. Set in line with very old fence east and in ζ of N-S Road. Mea. to stream 7:00 chains by GLO record fits very well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| D-7. DNR Monument.
3" cedar N39W - 12.4'
5" cedar S87W - 33.7'
4" cedar S55W - 8.7'
9" cedar N86E - 8.4' | E-6. DNR Monument.
5" cedar S62W - 27.4'
8" sugar maple N74W - 49.5'
10" Balm of Gilead N30E - 51.0'
8" balsam S52E - 29.1' |
|--|---|

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by David B. Babbitt Date 6-11-86
 Surveyor's Michigan License No. 21558