

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------------|
| 1. Public Land Survey | T | <u>42N</u> | R | <u>22W</u> | <u>D-8, D-9.</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 4/16/, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 D-8. Center 1/4 corner of Section 20. Not previously est.

D-9. S 1/4 corner of Section 20. Wood Post. Cedar 12 - S34E - 25 Lks.
 Cedar 18 - N64W - 21 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-8. Set at the intersection of the N-S and E-W 1/4 lines of Section 20 by closed traverse.

D-9. Set in line with fence south and in c of E-W road. OBT's would fall in roadway.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|----------------------|----------------------------|
| D-8. DNR Monument. | D-9. DNR Monument (buried) |
| 4" b. ash S32W 4.8' | 3" cedar N8W - 44.75' |
| 6" b. ash N38W 24.6' | 3" cedar N50W - 63.7' |
| 4" balsam S79E 10.2' | 5" cedar S68E - 44.1' |
| 5" b. ash N67W 1.1' | 5" cedar S11W - 41.65' |

Signed by David B. Babbitt

Date 6-11-86

Surveyor's Michigan License No. 21558