

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Delta</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>20</u> T <u>42N</u> R <u>22W</u>	<u>9, 8, 3.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 4/16, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

9. E 1/6 corner on E&W 1/4 line of Section 20. Not previously est.
8. W 1/16 corner on the E&W 1/4 line of Section 20. Not previously est.
3. North 1/16 corner on the west section line of Section 20. Not previously est.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

9. Set M.P.O.L. between the E 1/4 corner and the center of Section 20.
8. Set M.P.O.L. between the W 1/4 corner and the center of Section 20.
3. Set M.P.O.L. between the West 1/4 corner and the NW section corner of Section 20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                        |                          |                                   |
|------------------------|--------------------------|-----------------------------------|
| 9. DNR Monument.       | 8. DNR Monument.         | 3. 1" pipe driven in winter road. |
| b. ash 6" N12W - 15.7' | 7" cedar N70W - 37.1'    | 7" cedar S26W - 35.2'             |
| b. ash 5" N81E - 4.0'  | 6" r. maple N75E - 12.0' | 4" cedar S74W - 31.9'             |
| b. ash 7" S43W - 13.2' | 8" r. maple S17E - 15.0' | 6" cedar N20E - 10.35'            |
| cedar 6" N50W - 30.8'  | 8" balsam S20W - 39.0'   | 4" cedar S81E - 33.5'             |

Signed by David B. Babbitt Date 6-11-86  
 Surveyor's Michigan License No. 21558