

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Delta</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>17</u> T <u>42N</u> R <u>22W</u>	<u>14., 1., &amp; 16.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 4/17, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 14. South 1/16 cor. on the east section line of Section 17.  
Not previously est.
- 1. West 1/16 cor. on the north section line of Section 17.  
Not previously est.
- 16. East 1/16 corner on the south section line of Section 17.  
Not previously est.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 14. Set M.P.O.L. between the E 1/4 corner and the SE section corner of Section 17.
- 1. Set M.P.O.L. between the N 1/4 corner and the NW section corner of Section 17.
- 16. Set M.P.O.L. between the south 1/4 cor. and the SE section corner of Section 17.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                             |                           |                     |
|-----------------------------|---------------------------|---------------------|
| 14. DNR Monument.           | 1. DNR Monument.          | 16. DNR Monument.   |
| 4" b. cherry N40W - 101.95' | 8" maple S19E - 14.7'     | 5" cedar N70W 3.9'  |
| 9" w. spruce S30W - 81.30'  | 6" bl. ash S80W - 15.9'   | 4" cedar N5E 10.5'  |
| 4" r. maple S42E - 69.59'   | Tw. 4" maples N36E - 9.1' | 10" cedar N70E 1.9' |
| 4" b. ash N71E - 42.10'     | 6" maple N73E - 13.1'     | 8" cedar S45E 7.6'  |

Signed by David B. Babbitt Date 6-11-86  
 Surveyor's Michigan License No. 21558