

OK. Babbitt

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta (County) Located In: Corner Code --#
1. Public Land Survey T 42N R 22W H-7, H-6.
2. Property Controlling in Section S 15 T 42N R 22W 5, 12.
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, David B. Babbitt in a field survey on 10/28/87, 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

- A. Description of original monument and accessories and/or subsequent restoration:
H-7. South 1/4 corner of Section 15. Wood post. Cedar 14, S68W, 44 Lks. DO 10, N40E, 3 Lks.
H-6. Center 1/4 corner of Section 15. No previous record.
5. North 1/16 corner of Section 15. No previous record.
12. South 1/16 corner of Section 15. No previous record.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-7. Set on line between the SE and SW section corners of Section 15 and in line with a very old fence south.
H-6. Set at the intersection of the N-S and E-W 1/4 lines of Section 15 by closed traverse.
5. Set MPOL between the north 1/4 corner and the center of Section 15.
12. Set MPOL between the S1/4 corner and the center of Section 15.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-7. DNR Monument 10" cedar, N29E 60.2'
9" cedar N1E 72.6'
8" cedar N48W 42.5'
12" cedar N73W 31.9'
H-6. DNR Monument 3" cedar N7E 18.2'
5" cedar S55E 16.2'
6" cedar S15W 15.8'
6" cedar N89W 20.5'
5. DNR Monument 4" sugar maple S70W 37.3'
5" spruce N5W 1.65'
6" sugar maple N66E 18.4'
5" sugar maple S50E 16.6'
12. DNR Monument 6" balsam fir N62E 6.2'
5" " S32E 15.2'
4" " S68W 11.0'
5" " N13W 7.6'

Signed by David B. Babbitt
Surveyor's Michigan License No. 21558

Date 12-3-87