

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Delta</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T <u>42N</u> R <u>22W</u>	<u>J-3, K-2, K-3.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on July 6th, 1987, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J-3. South 1/4 corner of Section 2. Wood post. Cedar 18" - S55W, 11 Lks.
Cedar 14" - N48E, 14 Lks.
- K-2. East 1/4 corner of Section 2. Wood post. Spruce 10" - S49E, 37 Lks.
Cedar 10" - N66W, 14 Lks.
- K-3. Southeast section corner of Section 2. Wood post. Fir 10" - S62W, 31 Lks.
Hemlock 10" - N35E, 6 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-3. Set MPOL between the SE and SW section corners of Section 2. There are several cedar stumps in the area but I could not identify any as OBT's.
- K-2. In 1917 Marcus McNabb records having found both OBT's - "Cedar tree NWly. and spruce stub SEly. of stake." I found dead cedar broken off with trunk lying on ground south-easterly from stump. Stump and bottom of tree trunk are badly burned but part of upper blaze is intact with very definite axe marks but the scribing is all burned off. Set monument by GLO record from cedar OBT.
- K-3. Found 3/4" pipe in place. This pipe was not on record but fits the GLO record West, 22.96 chains, to a stream and measurements North to the East 1/4 corner of Section 2 is 2653.41 and South to the East 1/4 corner of Section 11 is 2654.13. I find no reason to question this position. Replaced pipe with DNR monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|------------------------|-------------------------|-----------------------------|
| J-3. DNR Monument | K-2. DNR Monument | K-3. DNR Monument |
| 4" Maple, S68E, 7.2' | 8" Maple, S57W, 29.7' | 6" Sugar Maple, S50E, 22.7' |
| 8" Maple, N32W, 5.25' | 14" Cedar, N15W, 33.15' | 9" Sugar Maple, S26W, 6.2' |
| 7" Maple, N5W, 24.05' | 6" Cedar, N16E, 47.5' | 9" Sugar Maple, N55W, 4.2' |
| 13" Maple, N37E, 38.4' | 8" Cedar, N52E, 54.0' | 4" Sugar Maple, N13E, 10.2' |

Signed by David B. Babbitt

Date 12-3-87

Surveyor's Michigan License No. 21558