

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Delta  
(County)

Located In:

Corner Code ~~##~~

- |                                       |     |       |       |
|---------------------------------------|-----|-------|-------|
| 1. Public Land Survey                 | T   | R     |       |
|                                       | T   | R     |       |
|                                       | T   | R     |       |
|                                       | T   | R     |       |
| 2. Property Controlling<br>in Section | S 2 | T 42N | R 22W |
|                                       | S   | T     | R     |
| 3. Miscellaneous<br>Property in Sec.  | S   | T     | R     |
|                                       | S   | T     | R     |

15, 16, 14

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on July 1st, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 15 West 1/16 on South section line at Section 2. No previous record.  
 16 East 1/16 corner on the South section line at Section 2. No previous record.  
 14 South 1/16 corner on the East section line at Section 2. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 15 Set MPOL between the South 1/4 corner and the SW section corner of Section 2.  
 16 Set MPOL between the South 1/4 corner and the SE section corner of Section 2.  
 14 Set MPOL between the East 1/4 corner and the SE section corner of Section 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                          |                          |                             |
|--------------------------|--------------------------|-----------------------------|
| 15 DNR Monument          | 16 DNR Monument          | 14 DNR Monument             |
| 8" Maple - S56E - 36.4'  | 4" Maple - S48E - 17.0'  | 7" R. Maple - N31E - 21.2'  |
| 3" Maple - S39W - 22.9'  | 9" Maple - S21W - 29.0'  | 7" R. Maple - S27E - 22.65' |
| 13" Maple - N82W - 33.0' | 13" Maple - N70W - 16.0' | 5" R. Maple - S31W - 40.4'  |
| 12" Maple - N 4W - 80.1' | 17" Maple - N 8W - 5.6'  | 10" Spruce - N74W - 3.9'    |

Signed by David B. Babbitt

Date 12-3-87

Surveyor's Michigan License No. 21558