

OK
d.l.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta
(County)

Located In:

Corner Code ##

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>42N</u> | R | <u>22W</u> | <u>K-1</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 7/8, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1. NE section corner of Section 2. Michigan D.N.R. 1971 1" pipe w/4" aluminum cap.
7" h.maple, N6E, 27.8'
8" h.maple, S25E, 50.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1. Found 1" pipe w/4" DNR aluminum cap. Both DNR NBT's have been destroyed. Rewitnessed monument as found. Monument is on east edge of logging road and is in some danger of being knocked out.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1. DNR Monument.
10" h.maple N40E, 44.55'
8" h.maple S86E, 50.95'
10" cedar S60W, 58.15'
8" balsam N74W, 49.4'

Signed by David B. Babbitt Date 12-3-87

Surveyor's Michigan License No. 21558