

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Delta</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>42N</u> R <u>22W</u>	<u>1-7, J-7.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 7/8, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1-7. SW section corner of Section 14. M.S. McNabb, 1919. Original cedar BT, S38W, 17.1'
 Cedar stump 12, N73W, 20.2'
 Balsam stub N65W, 18'

J-7. South 1/4 cor. of Section 14. M.S. McNabb - 1919. Orig. Elm BT down plain.
 Maple 6" N65E, 19.75'
 Maple 9" North 30.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-7. In 1937 the USFS recorded "corner consists of a stake" and "the corner is on an old fence line". Presumably this is the same point that McNabb recorded in 1919. Could not find any evidence of the original survey or McNabb's post or NBT's. Set DNR monument at corner of very old fence south and east as indicated in the USFS record. Mea. east to the S 1/4 cor. of Section 14 is very near what McNabb recorded in 1919.

J-7. In 1937 the USFS recorded "sq. post 1 ft. south of a 6" fence post with a metal tag on the north side of it." Presumably this was McNabb's 1/4 post. I found the fence post with metal tag down but still in place and a sq. cedar post lying nearby. Set DNR monument 1 ft. south of fence post bottom as recorded by USFS. Mea. to SE and SW section corners of Section 14 are very near what McNabb record calls for.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-7. DNR Monument
 7" cedar S47W, 47.4'
 6" balsam N24W, 34.3'
 8" maple N42E, 45.95'
 8" w.spruce S16E, 44.1'

J-7. DNR Monument
 4" maple N68W, 11.05'
 8" maple N9W, 57.8'
 10" maple N30E, 40.5'
 5" maple S30E, 28.75'

Signed by David B. Babbitt

Date 12-3-87

Surveyor's Michigan License No. 21558