

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Delta</u> <small>(County)</small>	Located In:	Corner Code <u>77</u>
1. Public Land Survey	T <u>42N</u> R <u>22W</u>	<u>I-4, G-4, G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David Babbitt, in a field survey on July 1st, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-4 East ¼ corner of Section 10. Wood Post. Hemlock 24 - S35E - 17 Lks.
Elm 12 - N45W - 22 Lks.
- G-4 West ¼ corner of Section 10. Wood Post. Cedar 6 - S40W - 28 Lks.
Tamarack 16 - N30E - 27 Lks.
- G-5 Southwest section corner of Section 10. Wood Post. Lynn 20 - S35E - 37 Lks.
Cedar 18 - N65W - 35 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-4 Set MPOL between the NE and SE section corners of Section 10.
- G-4 Set MPOL between the NW and SW section corners of Section 10. There are several large Tamarack blow downs and some Cedar stumps in the area but I could not identify any as O.B.T.'s
- G-5 Set by double proportion to the record of the original Gov't. Survey using ¼ corners 1½ miles West and 1½ miles East and section corners 1 mile North and 1 mile South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---------------------------|--------------------------|--------------------------------|
| I-4 DNR Monument | G-4 DNR Monument | G-5 DNR Monument |
| 6" Bl. Ash - N65W - 27.4' | 14" Cedar - N58E - 35.8' | 8" Sugar Maple - S80W - 7.15' |
| 7" Maple - N 4E - 18.7' | 4" Balsam - S62E - 16.8' | 4" Sugar Maple - S30E - 9.8' |
| 4" Maple - N15E - 11.75' | 14" Cedar - S33W - 32.9' | 10" Sugar Maple - N30E - 15.1' |
| 8" Y. Birch- S 7E - 19.9' | 12" Cedar - N88W - 6.9' | 4" Sugar Maple - N 8W - 14.5' |

Signed by David B. Babbitt Date 12-3-87
 Surveyor's Michigan License No. 21558