

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Delta</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>42N</u> R <u>22W</u>	<u>H-5, I-6, G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, David Babbitt, in a field survey on July 16th, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H-5 North ¼ corner of Section 15. Wood Post. Sugar 8 - S64W - 13 Lks.  
Sugar 18 - N60E - 13 Lks.
- I-6 East ¼ corner of Section 15. M. McNabb - 1922 - Stake in Place  
Hemlock 8 - N75W - 16.5'  
Ash 10 - S62E - 21.2'
- G-6 West ¼ corner of Section 15. M. McNabb - 1922 - Stake  
Cedar 7 - N55E - 24'  
Cedar 4 - S12W - 10.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-5 Set MPOL between the NE and NW section corners of Section 15.
- I-6 Set MPOL between the NE and SE section corners of Section 15. No sign of McNabb's post or N.B.T.'s.
- G-6 Set MPOL between the NW and SW section corners of Section 15. No sign of McNabb's post or N.B.T.'s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                               |  |                            |                         |
|-------------------------------|--|----------------------------|-------------------------|
| H-5 DNR Monument              |  | I-6 DNR Monument           | G-6 DNR Monument        |
| 5" Sugar Maple - N07W - 23.0' |  | 4" Balsam - S 2E - 21.1'   | 8" Cedar - S78E - 30.2' |
| 6" Sugar Maple - N70E - 27.4' |  | 9" Spruce - S21W - 41.3'   | 7" Cedar - S 8E - 28.8' |
| 6" Sugar Maple - S31W - 24.9' |  | 8" Maple - N67W - 41.9'    | 6" Cedar - S53W - 42.7' |
| 8" Sugar Maple - N46W - 15.1' |  | 4" Y. Birch - N29E - 40.3' | 7" Cedar - N52W - 22.3' |

Signed by David B. Babbitt Date 12-3-87  
 Surveyor's Michigan License No. 21558