

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta
(County)

Located In:

Corner Code ~~##~~

- | | | | |
|------------------------------------|------|-------------|---------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S 15 | T 42N R 22W | 2, 1, 3 |
| | S | T | R |
| 3. Miscellaneous | S | T | R |
| Property in Sec. | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on July 16th, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 2 East 1/16 corner on the North section line of Section 15. No previous record.
 1 West 1/16 corner on the North section line of Section 15. No previous record.
 3 North 1/16 corner on the West section line of Section 15. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 2 Set MPOL between the North 1/4 corner and the NE section corner of Section 15.
 1 Set MPOL between the North 1/4 corner and the NW section corner of Section 15.
 3 Set MPOL between the West 1/4 corner and the NW section corner of Section 15.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-------------------------------|--------------------------------|--------------------------|
| 2 DNR Monument | 1 DNR Monument | 3 DNR Monument |
| 9" Sugar Maple - N53E - 17.2' | 14" Sugar Maple - S61E - 26.6' | 6" Maple - N72E - 6.05' |
| 7" Sugar Maple - S40W - 15.8' | 15" Lynn - S10E - 31.8' | 6" Maple - S21E - 47.0' |
| 5" Sugar Maple - N46W - 40.7' | 6" Sugar Maple - N24W - 11.8' | 4" Maple - S27W - 34.7' |
| 5" Sugar Maple - N20W - 44.2' | 9" Sugar Maple - N32E - 7.8' | 5" Balsam - N85W - 25.1' |

Signed by David B. Babbitt

Date 12-3-87

Surveyor's Michigan License No. 21558