

018213

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Delta</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>17</u> T <u>42N</u> R <u>22W</u>	<u>13, 2.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 12/29/86, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 13. SE 1/16 corner of Section 17. No previous record.
- 2. E 1/16 corner on the north section line of Section 17. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 13. Set at the computed center of the SE 1/4 of Section 17 by closed traverse.
- 2. Set MPOL between the NE section corner and the N 1/4 corner of Section 17.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---------------------------|---------------------|
| 13. DNR Monument | 2. DNR Monument |
| 5" cedar, S32W, 8.1' | 7" ash, N24W, 11.4' |
| 6" b.spruce, N40W, 10.45' | 7" ash, N74E, 9.3' |
| 7" cedar, N66E, 19.2' | 4" ash, S18W, 4.3' |
| 4" cedar, S70E, 7.85' | 8" ash, S75W, 10.9' |

Signed by David B. Babbitt Date 9-29-88
Surveyor's Michigan License No. 21558