

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---|---------------------------|------------------|
| <u>Delta</u> <small>(County)</small> | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>42N</u> R <u>22W</u> | <u>C-2, C-3.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, David B. Babbitt, in a field survey on 5/19/88, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-2. E1/4 corner of Section 6. Marcus McNabb, reset new stake & bearing stakes NE & SW 33'.
- C-3. NW section corner of Section 8. Wood post. Cedar 10, S58W, 18 lks.
Cedar 14, N48E, 22 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-2. Marcus McNabb states that he found a wood stake and one OBT N70E, 152'. I found what I believe to be Marcus McNabb's "new stake" a sq. cedar post about 4" in diameter rotted off and fallen down. Old sq. post is in a N-S fence line and fits McNabb's mea. north to the NE section corner of Section 6 quite well. Set DNR monument in place of post.
- C-3. Found fragments of cedar one of which has a definite hack mark partly healed over for the measuring notch from the southwest OBT. I could not tell exactly where the tree stood when alive but set the monument from the spot where the notch was found. No sign of the northeast OBT—swamp edge 108 lks. East fits well and it is very near the single prop. mea. between the 1/4 corner, 1/2 mile north and the section corner 1 mile south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-----------------------|-----------------------|
| C-2. DNR Monument. | C-3. DNR Monument. |
| 8" cedar, N75E, 18.4' | 8" cedar, N4W, 68.7' |
| 6" cedar, S52E, 6.6' | 6" cedar, N70E, 27.7' |
| 6" cedar, S2E, 26.05' | 8" cedar, S28E, 40.8' |
| 7" cedar, S88W, 28.4' | 6" cedar, S5W, 61.2' |

Signed by David B. Babbitt Date 9-29-88
 Surveyor's Michigan License No. 21558