

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S 25 T 42N R 22W	3
	S 25 T 42N R 22W	11
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jul 21 1997

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (8) West One-sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.
- (11) Southwest One-sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (8) Corner position established mid-point and on-line between the West and Center Quarter corners of Section 25.
- (11) Corner position established at the intersection of the South and West One-sixteenth lines of Section 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--------------------------------------|-----------------------------------|
| (8) DNR monument | (11) DNR monument |
| 4" B. Spruce N34E 26.8' (1/16S, BT) | 10" Cedar N39E 11.55' (1/16S, BT) |
| 5" B. Spruce S18W 15.25' (1/16S, BT) | 12" Cedar S19E 18.05' (1/16S, BT) |
| 6" B. Spruce N71W 7.7' (1/16S, BT) | 06" Cedar S64W 4.1' (1/16S, BT) |
| 5" B. Spruce N11W 19.35' (1/16S, BT) | 07" Cedar N13W 3.85' (1/16S, BT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division