

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Delta
(County)

Table with columns: Located In, Corner Code #. Rows include Public Land Survey (T 42N R 22W, K10, K12), Property Controlling in Section (S, T, R), and Miscellaneous Property in Sec. (S, T, R).

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

K12 Jul 31 1997
K10 Jul 17 1997

I, Paul R. Bressette, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numerical values and symbols (dots) at specific grid intersections.

A. Description of original monument and accessories and/or subsequent restoration:

(K10) Quarter corner common to Sections 25 and 26. 1852: E.C. Martin, D.S. Set wood post witnessed by: Hemlock 14 S40E 56 lks.; Hemlock 8 N58W 37 lks. No record evidence of corner perpetuation or restoration found.
(K12) Quarter corner common to Sections 35 and 36. 1852: E.C. Martin, D.S. Set wood post witnessed by: Hemlock 14 S20E 23 lks.; Cedar 18 N68W 18 lks. No record evidence of corner perpetuation or restoration found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K10) No evidence of original survey or subsequent restoration found. Corner location falls in area of extensive cutting with same ownership all around corner. Corner position re-established mid-point and on-line between the Northwest and Southwest corners of Section 25, and is accepted as a careful and faithful RE-ESTABLISHMENT of the position of the original corner.
(K12) No evidence of original survey or subsequent restoration found. Corner location falls in very large clearcut that has been replanted. Corner position re-established mid-point and on-line between the Southwest and Northwest corners of Section 36, and is accepted as a careful and faithful RE-ESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K10) DNR monument: 10" R.Maple N41E 49.25' (1/4S,NBT), 05" Aspen S26E 13.4' (1/4S,NBT), 08" R.Maple S13W 32.8' (1/4S,NBT), 09" Sugar N44W 25.35' (1/4S,NBT). All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.
(K12) DNR monument: 02" Balsam N14E 18.0', 12" Cedar stump N72E 6.2', 02" Tamarack S24E 9.65', 02" Balsam N72W 12.2'. All trees are blazed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
Surveyor's Michigan License No. 37270

Date

For the Michigan Department of Natural Resources - Forest Management Division